

MISSION OPERATIONS DIRECTORATE FLIGHT DIRECTOR OFFICE



STS-100/6A MISSION SUMMARY

FLIGHT READINESS REVIEW

April 5, 2001

**DA8/P. L. Engelauf
DA8/J. M. Curry**

STS-100/6A Shuttle Overview

- **OV-105 – Endeavour**
- **Crew – 6 US, 1 Russian**
(No crew exchange)
- **Mission Duration 11+1+2**
- **7 N2 tanks**
- **5 Cryo Tanks sets**
 - **Cryo margins positive for 11+1+2 mission with ~101 hours pad hold, H2 limited.**
- **Two Planned EVAs, One unscheduled EVA**
- **Propellant acceptable. Fwd ~ 700 #, Aft ~ 3000# margin**
- **Shuttle reboost planned, to be performed from these margins**

STS-100/6A Mission Summary

- **Four primary objectives for STS-100, in priority order:**
 - 1.) SSRMS Delivery and checkout**
 - EVA Deployment and power connection/transfer
 - Critical path for airlock delivery on 7A
 - 2.) Delivery of critical consumable supplies from MPLM**
 - 3.) Outfit US Lab with Express Racks and transfer Utilization Experiments**
 - 2 Express racks
 - Resupply Stowage Racks, Resupply Stowage Platforms
 - Four powered payloads carried in shuttle middeck
 - 4.) Delivery of on-orbit spares**
 - DC Switching Unit (DCSU)
 - Video Signal Conditioner (VSC)

STS-100/6A Critical Activities

To preserve the assembly sequence, 6A must achieve minimum functionality for the SSRMS to allow airlock placement on 7A

Activities required:

- Rendezvous/dock**
- Transfer SLP to Lab and deploy SSRMS via EVA**
- ‘Walkoff’ SSRMS onto Lab PDGF**
- Transfer power from SLP to Lab PDGF***
 - Possible to do on Expedition EVA**
- Berth MPLM and remove/install (critical) cargo**
- Remove MPLM**

This mission would require a minimum of 6 days (3 docked)


6A Mission Overview

- **FD1**
 - Launch
- **FD2**
 - Activate and checkout OIUs
 - SRMS Checkout
 - EMU checkout
 - Activate and checkout Orbiter Docking System
 - OSVS Checkout
 - Orbiter Cabin depress to 10.2 psi


6A Mission Overview

- **FD3**
 - **Activate APCUs**
 - **ISS Maneuver to Docking Attitude**
 - **ISS Feather Solar Arrays for Docking (P6, FGB, SM)**
 - **Perform +Vbar ISS rendezvous**
 - **Dock Orbiter to PMA2**
 - **Exchange key items via PMA2 (No Ingress)**
 - **To ISS:**
 - **RWS UOP Bypass Cables**
 - **Video Crosswire Cables**
 - **PCS Software Upgrade CD**
 - **CWC's, IMAX Film, ODF**
 - **From ISS:**
 - **Spare PGT For EVA**

6A Docking to ISS



6A Initial Configuration




STS-100/6A Msn Summary

6A Mission Overview

- **FD4**
 - **SRMS transfer of SLP to Lab Cradle Assembly**
 - **EVA 1**
 - **Connect power to SLP via J300 Umbilical, activate keep-alive power**
 - **Transfer ISS UHF antenna from SLP to Lab**
 - **Remove restraints (Superbolts) from SSRMS**
 - **Initial boom raise (manual)**
 - **Unfold boom segments and secure in onorbit configuration**
 - **Raise SSRMS booms (Robotic)**
 - **When SSRMS reaches operational temp, use shoulder joint to raise booms**
 - **Orbiter 14.7 psi Repress (During EVA)**

6A after EVA 1/SSRMS Transfer




STS-100/6A Msn Summary

6A Mission Overview

- **FD5**
 - **Open Hatches (First full ingress this mission)**
 - **SSRMS Initial checkout (Joint tests), Lab PDGF Grapple**
 - **Install MPLM on Node Nadir using SRMS**
 - **ISS crew performs MPLM vestibule outfitting/MPLM activation**
 - **Close hatches, 10.2 depress**


6A After MPLM Transfer



6A Mission Overview

- **FD6**
 - ISS crew performs rack transfers from MPLM
 - Shuttle crew EVA #2
 - J400 Power reconfig to power PDGF on Lab
 - Remove starboard Early Comm antenna from Node, VSC from SLP
 - Transfer DCSU to External Stowage Platform (ESP) on Lab
 - Repress to 14.7, open hatches

6A after EVA 2



STS-100/6A Msn Summary


6A Mission Overview

- **FD7**
 - **SSRMS 'Loaded Checkout' with SLP**
 - **Handoff SLP to SRMS, berth in Shuttle PLB**
 - **Powered payload transfers**
 - **MPLM Transfers**
- **FD8**
 - **EVA 3 if required; otherwise – transfers, Additional SSRMs Checks**
 - **SSRMS Airlock Installation Dry Run**
- **FD9**
 - **MPLM Vestibule Deoutfitting, depress, leak checks**
 - **SSRMS Unloaded Dynamic Checkout**
 - **MPLM stow in Orbiter Payload Bay**
 - **Crew conference**

6A Mission Overview

- **FD10**
 - Close Hatches
 - Undock from PMA2, Flyaround (ICBC Filming), Separate
 - Cabin Stow
- **FD11**
 - FCS C/O, RCS Hot-fire, Cabin Stow
 - Off duty for second half of day
- **FD12**
 - D/O Prep
 - Landing 10/18:54

Undock/Flyaround Sequence



STS-100/6A Msn Summary

Soyuz/STS-100 Launch Conflict Issues

Considerations Affecting the Choice
Of STS-100 Launch Date

Current Plan

- The baseline plan for these launches:
 - 6A Shuttle launches on 4/19
 - 2Soyuz begins fueling and final irreversible launch processing after confirmation of 6A launch on 4/19
 - 6A Shuttle nominal undock on 4/28
 - 2Soyuz launches on 4/28 and docks to ISS on 4/30
- Considerations
 - Accommodates Russian request to avoid May Day holidays
 - If 6A undocks 4/28, crew will only have one day off vice 2 that are baselined between shuttle undocking and Soyuz docking
 - Regardless of the undocking day, the last crew off-duty time will have been half day on April 14 and half day on April 15 (i.e., will have worked 13-14 days continuous)

Shuttle Launch Considerations

- Shuttle Launch Constraints
 - Range unavailable May 11-19
 - Beta angle cutout May 18 – June 7
 - No Arrivals/Departures during shuttle docked period
 - ISS Food depletion estimated June 1
 - Shuttle or Progress can resupply
 - Progress launch on May 20 is first flight of upgraded booster
- Soyuz Launch Constraints
 - New Soyuz (S2) Must Launch By May 11
 - Onorbit Soyuz 1 reaches 200 day Life Limit
 - S2 Arrival requires P3 undock, S1 flyaround to clear port
 - 2-day timeline impact
- Protecting two days between shuttle undocking and Soyuz docking is prudent

Mission Impacts of Options

- If STS-100 Launches before Soyuz 2:
 - PRO:
 - Maximizes Shuttle launch opportunities
 - Maximizes margin for ISS food resupply
 - Supported by existing flight products (flight plan, thermal analysis, etc.)
 - CON
 - Shuttle must stand down for Soyuz if not launched before Soyuz mandatory launch date
 - Aggressive ISS crew schedule – no rest between 6A and 2 Soyuz
 - Reboost option constrained by Soyuz phasing requirements, however, reboost can still be performed

Mission Impacts of Options

- If Soyuz launches before STS-100
 - PRO
 - Minimizes impacts to ISS crew for 6A stage operations
 - Soyuz changeout and visiting crew activities 'out of the way' before 6A cargo and robotics operations
 - CON
 - Significant mission rework
 - Shuttle and ISS crew sleep cycles mismatched by ~ 6 hours due to shuttle planar launch window shift
 - May be able to minimize impact with descending landing opportunities
 - Must work around range availability and Beta constraints
 - Reduces overall number of shuttle launch attempts

Launch Option 1

- Current NASA Plan:
 - Protect Shuttle launch attempts from April 19 until May 1
 - If no launch by May 1, stand down for Soyuz launch on 10 May
 - Earliest Soyuz date if launch processing cannot start until shuttle launch/stand down decision
 - Soyuz slips day for day based on shuttle launch, or targets for May 10 a priori
 - Day for day slip minimizes time between STS-100 undock and S2 arrival, but maximizes Soyuz launch opportunity
 - May 10 target minimizes margin for onorbit 1Soyuz lifetime, but provides best possible ISS crew schedule

Launch Option 2

- Rosaviakosmos Plan
 - Soyuz 2 launch April 28, independent of shuttle launch slip
 - Protects Russian holidays May 1,2 and 9.
 - Accommodates shuttle launch only on April 19. April 20 launch would require mission duration constraints.
 - NASA position is that Soyuz docking with shuttle present is not allowed
 - Clearance concerns for FGB nadir approach
 - Loads assessment required for SM aft dockings
 - If shuttle does not launch on April 19, next window is post Soyuz 1 sep, May 6, until range cutout, May 10.
 - Assumes no Soyuz delay, or shuttle takes priority for May 6 date
 - Next opportunity is June 8

Summary

- The basic decision point is whether to launch STS-100 before the 2Soyuz or after
 - ‘Before’ maximizes shuttle launch opportunities (12) and resupply consumables margin, but complicates 6A stage crew ops
 - ‘After’ results in reduced shuttle launch opportunities (5) but simplifies stage operations
- If Soyuz does not move from April 28, need to decide whether to attempt April 19 or stand down to May 6
 - If no launch on April 19, still have the chance to make May 6-10
 - If no launch in May, slip until June 8