

EXTERNAL TANK



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama




STS-103/ET-101

Flight Readiness Review

External Tank Project



Ron Wetmore
November 19, 1999



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama




Overview

Presenter Ron Wetmore

Date 11/19/99

Page 2

- **ET-101 Highlights**
 - Fourth ET to fly with SRB camera coverage
- **Limited life component status - All items within required life**
- **Processing anomalies**
 - ET/SRB Cross-Strap Harness Failures - Discussed by USA
 - ET-106 GO2 2" Disconnect Bent Poppet Stem Missing Chrome Plating
 - STS-103/ET-101 hardware assessment - Discussed by BNA
- **Requirement Changes**
 - LH2 Tank Changes for SSME Block II Implementation
- **Changes resulting from Intertank thrust panel foam loss**
 - Increased Intertank Foam Venting
- **Special Topic**
 - Weld Instruction Card (WIC) Certification
 - Heat Treat of Flexible Joint Ball
- **Open work/paper - No constraints to flight**



LH2 Tank Changes for SSME Block II Implementation

Presenter Ron Wetmore

Date 11/19/99

Page 3

- **Change**

- Revised LH2 tank vent/relief valve acceptance pressure requirements and post proof x-ray requirements

- **Background**

- Advanced high pressure fuel turbopump in the Block II SSME has increased preburner temperature spikes during engine start transient causing reduced turbine blade life
 - PSIG action resulted in decision to modify the Block II start transient by increasing the LH2 inlet pressure at engine start command
 - Required modification of the ET pre-pressurization control bands and LH2 ullage pressure ICD
- Raised pre-pressurization control band will be used only on flights with three Block II SSMEs
 - **Not required for STS-103/ET-101**

- **Description**

- Revised ET GH2 vent/relief valve requirements for higher pre-press level - No design change

	Was	Now
• Relief pressure	36.0 \pm 1.0 psig	36.75+0.25/-0.00 psig
• Reseat pressure	34.0 psig	34.25 psig

- Revised post proof weld x-ray requirements for LH2 tank circumferential welds



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama



LH2 Tank Changes for SSME Block II Implementation

Presenter Ron Wetmore

Date 11/19/99

Page 4

- **Basis for Certification**

- **Test and Inspection**

- Successful completion of LH2 tank proof test
 - Performed post proof weld x-ray requirements on additional 215 inches of LH2 tank circumferential welds
 - No change to critical test demonstrated LH2 tank Factor of Safety
 - Raised LH2 tank pre-press band was demonstrated on STS-91 tanking test
 - Narrow band with 0.5 second GHe bursts was demonstrated
 - Pre-press level demonstrated was 0.3 psi lower than planned for use with three Block II SSMEs

- **Analysis**

- Propulsion analysis shows LH2 tank ullage pressure will be within LCC limits during pre-press
 - Structural analysis shows overall critical factor of safety unchanged
 - Factor of Safety for critical circumferential welds (failure mode: ultimate tension)

<u>Weld ID</u>	<u>Required</u>	<u>Was</u>	<u>Now</u>
• LH2 Tank H4	1.25	1.51	1.45
• LH2 Tank H5	1.25	1.49	1.42



Intertank Foam Venting

Presenter Ron Wetmore

Date 11/19/99


Page 5

- **Change**

- Increased vented portions of the Intertank thrust panel and skin/stringer panel foam

- **Background**

- Post flight inspection of STS-87 revealed out-of-family damage to the Orbiter tiles caused by foam loss from the ET Intertank thrust panel
- A rigorous test program has demonstrated that foam venting reduces popcorn-type debris
- Vented foam configuration has been certified by test and analysis to do no harm
- Venting of Intertank foam implemented on STS-96/ET-100 and STS-93/ET-99
- Review of SRB video following STS-96/ET-100 showed less debris with vented foam
- Based upon STS-96/ET-100 data and additional analysis, area of Intertank thrust panel foam to be vented was increased for STS-93/ET-99



Typical Vented Foam Configuration




Intertank Foam Venting


Presenter Ron Wetmore

Date 11/19/99

Page 6

• Background (continued)





Intertank Foam Venting


Presenter Ron Wetmore

Date 11/19/99



Page 7

- **Background (continued)**

- Review of STS-93/ET-99 SRB flight video confirmed performance enhancement realized through foam venting
 - Popcorning exhibited on Intertank skin/stringer foam



Typical Vented Foam Configuration



Vented Area on STS-96/ET-100 +Y Thrust Panel

Foam Loss on Skin/Stringer Areas



SPACE SHUTTLE PROGRAM

Space Shuttle Projects Office (MSFC)

NASA Marshall Space Flight Center, Huntsville, Alabama






Intertank Foam Venting


Presenter Ron Wetmore

Date 11/19/99


Page 8

Description of Change

- Perform venting of Intertank foam areas
 - Combination of BNA-identified debris zone and areas of observed foam loss
 - Areas of potential ice-formation and unmachined foam excluded
-  Vented thrust panel area in BNA-identified debris zone = 90 ft²
-  Vented thrust panel area outside of BNA-identified debris zone = 12 ft²
-  Vented skin/stringer areas = 725 ft²
- Unvented BNA-identified debris zone = 36 ft²
(8 ft² bathtubs, 18 ft² ramps, 10 ft² cryo)



Panels 6-8 omitted





Thrust Panel and Skin/Stringer Panel Foam Venting

Presenter Ron Wetmore

Date 11/19/99

Page 9

- **Basis for Certification**

- Test

- Tests performed in different test beds following various environmental conditioning
 - Results from all performance testing show that vented foam performs as well as or better than the non-vented foam configuration and measurably reduces foam loss

- Similarity

- Vented foam configuration similar to configuration flown on STS-96/ET-100 and STS-93/ET-99

Certification Test	No. of Tests	Humidity	Salt Fog	Vented
Vented Foam Certification Testing				
Mechanical Properties/Acceptance Testing				
Density	200			X
Bond Tension	540	X	X	X
Flatwise Tension	540	X	X	X
Lap Shear	360	X		X
Plug Pulls	144		X	X
Flexure (Ribbed panels)	24	X		X
Thermal Properties				
Thermal Conductivity	24	X	X	X
Flight Verification				
Hot Gas - Flat Panels, Machined foam	20	X	X	X
Hot Gas - Rib Panels, Machined foam	63	X	X	X
Hot Gas - Skin/stringer, Machined foam	7	X		X
Thermal/Vacuum, Flat Panels, Machined foam	40	X	X	X
Thermal/Vacuum, Single Rib Panels, Machined foam	14			X
Thermal/Vacuum, Rib Panels, Machined foam	24	X	X	X
Thermal/Vacuum, Skin/stringer, Machined foam	8	X		X
Wind Tunnel (AEDC), Machined foam	4			X
Vibro/Acoustic Test (DOE C Addendum Testing)	6	X		X
Process Verification/Acceptance				
Full-Scale Process Pathfinder (GVTA)	1			X



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama



Thrust Panel and Skin/Stringer Panel Foam Venting


Presenter Ron Wetmore

Date 11/19/99

Page 10

- **Basis for Certification**

- Popcorning performance of additional rib and skin/stringer configurations similar to that of previously successfully vented thrust panel configurations
- NASA/LMMSS IFA team reviewed test results indicates that venting of rib locations adjacent to circumferential rib ramps and skin/stringer panel areas are certified "to do no harm"
- No safety of flight concerns



Weld Instruction Card (WIC) Certification

Presenter Ron Wetmore

Date 11/19/99


Page 11

- **Issue**

- During a recent weld schedule review, it was determined that several of the weld schedules were incorrectly certified

- **Background**

- Weld certification requirements are established through Engineering process requirements documents
 - Certification requirements verify that weld schedules produce acceptable weld strengths and quality
 - Requirements are then restated and implemented in the "how to" manufacturing process documents
- Ambiguity of the weld process documents and reliance on institutional knowledge led to instances of incomplete testing for weld certification



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama



Weld Instruction Card (WIC) Certification


Presenter Ron Wetmore

Date 11/19/99

Page 12

• **Background**

- Performed LMMSS Quality and Engineering review of all “as-built” ET welds
 - Discrepancies were documented on non-conformance documents (NCDs)
 - Each NCD was individually analyzed, dispositioned and approved by LMMSS and NASA/MSFC
 - When necessary, additional welded panels were fabricated and tested
 - All discrepant weld schedules were reviewed to the correct certification condition
 - Weld operations were suspended until discrepancies were resolved
- Process escapes led to end-to-end weld process review
 - LMMSS and NASA/MSFC conducted a review (October - present) of all ET welding processes
 - No significant findings that required immediate implementation prior to weld operations resuming
 - 49 findings that require resolution:
 - Procedural enhancements
 - Communication/information flow down
 - Adherence to command media
 - Training enhancement opportunities
 - One additional issue identified during the NASA/LMMSS Review
 - Concern for design strength of welds (cryogenic properties) due to effect of weld parameter variations



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama



Weld Instruction Card (WIC) Certification

Presenter Ron Wetmore

Date 11/19/99

Page 13

- **STS-103/ET-101 Rationale for Flight**

- Team reviewed the 49 findings noted during the review and determined that there were no concerns for ET-101
- Team also conducted an assessment of the weld strength and determined that adequate rationale existed for ET-101 clearance:
 - Weld-by-weld reviews
 - Review of as-built parameter charts
 - ET-101 as-delivered weld tests
 - Parameter range test data
 - Wide panel and confidence panel data
 - Fracture property review
 - Proof test stresses and history
 - Flight stress analysis
- LMMSS and NASA/MSFC Review Team concluded that there was no safety of flight concerns
 - Resolution of remaining findings are not considered as constraints to flight
 - Root cause identified as lack of clear process requirements and lack of command media that controls of weld certifications
 - Corrective action plan in work



Heat Treat of Flexible Joint Ball

Presenter Ron Wetmore

Date 11/19/99


Page 14

- **Issue**

- Incorrect heat treat of Inconel 718 Ball Strut Tie-Rod Assembly (BSTRA) balls

- **Background**

- 24 BSTRA flexible joints on each ET
 - 19 balls in the GO2 and GH2 pressurization line joints
 - 5 balls in the LO2 feedline joints
- Both diameter balls affected by incorrect heat treat
 - Specification for Inconel Sheet/Tubing required for heat treatment of BSTRA balls
- BSTRA subcontractor recently determined that their heat treating vendor had incorrectly age hardened a large number of balls to a combination of the specifications for Inconel Sheet/Tubing and Inconel Bars/Forgings
 - ET feedline and pressurization line supplier discovered discrepancy during a review of data pack at LMMSS' request
- Test coupons accompanying suspect balls showed that the parts exceeded specification requirements
 - Tested at 40-41 Rockwell "C" (Rc) hardness
 - Specification requires minimum of 37 Rc




Heat Treat of Flexible Joint Ball


Presenter Ron Wetmore

Date 11/19/99


Page 15



Line Flexible Joint
(X-Section)



Ball Strut Tie-Rod Assembly
(LO2 Feedline 2.24" dia. ball shown)





Heat Treat of Flexible Joint Ball

Presenter Ron Wetmore

Date 11/19/99

Page 16





Heat Treat of Flexible Joint Ball

Presenter Ron Wetmore

Date 11/19/99

Page 17

- **Discussion**

- Suspect balls are also installed on the STS-103/ET-101 pressurization lines
- Review of build paper showed that balls of this pedigree have previously flown from the same heat treat lot with same hardness values
 - No anomalies noted
- LMMSS and NASA/MSFC metallurgists reviewed the differences in heat treat cycle and determined that the structural integrity of the BSTRA is unaffected

- **Rationale for Flight**

- Test
 - Qualification test remains valid
- Analysis
 - Significant stresses are compression
 - Minor differences in hardness values not sufficient to affect compression strength
 - Design FS > 4.0
- Acceptance
 - Test coupons had final acceptance values within acceptable limits
 - Rockwell "C" hardness = 40-41 vs requirement of 37
 - Hardness values for properly treated balls = 39-47 Rc



SPACE SHUTTLE PROGRAM
Space Shuttle Projects Office (MSFC)
NASA Marshall Space Flight Center, Huntsville, Alabama




Readiness Statement


Presenter Ron Wetmore

Date 11/19/99

Page 18

**The External Tank, ET-101, is hereby certified
and ready for STS-103 flight pending
completion/closure of open and planned work**


Terry L. Hibbard
Vice President, External Tank Project
Lockheed Martin Michoud Space Systems


Parker V. Counts
Manager, External Tank Project
Marshall Space Flight Center